534

	Description of work	Unit	Quantity in units	
			Traffic Inspector's quarters	Officers' Retiring Rooms
10.	Teakwood windows with batten shutters, iron bars, etc., complete.	S. ft.	160	30
11.	Do with glazed shutters, with iron bars, etc., complete.	,,	...	120
12.	Teakwood ventilators with glazed shutters, etc., complete.	,,	13	15
13.	Teakwood wrought and put up including wood oiling.	C.ft.	110	130
14.	Chocolate painting to doors and windows ...	100 S.ft.	10	10
15.	Hoisting and fixing 41¼ lbs. sec. rails for roof (labour only).	R.ft.	70	..
16.	Roofing with 1st class Mangalore tiles on teak reepers 2" x 1" including chunam borders (with tiles supplied by the Deptt.)	100 S.ft.	18	33
17.	Ridge tiles set in mortar (with departmental tiles).	R.ft.	50	120
18.	Flooring with Mangalore tiles on 3" concrete (tiled supplied departmentally) including cement pointing.	100 S.ft.	...	10
19.	Flooring with Cuddapah slabs on 3" concrete (slabs supplied departmentally) including cement pointing.	,,	10	6
20.	White washing two coats	,,	71	70
21.	Chunam plastering	,,	71	70
22.	Cut stone pillars with capitals and bases ...	Each	...	10

Y. K. RAMACHANDRA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 24th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 23rd February 1929, for constructing Police lines at Bastihalli, Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 250 in cash as earnest money, and be superscribed "Tender for constructing Police lines at Bastihalli, Chitaldrug Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for constructing Police lines for one Daffedar and for Constables at Bastihalli, Chitaldrug Taluk.

No.	Items of work	Per	Quantity
1	Earthwork excavation foundation and filling in basement including watering and tamping, etc., complete.	C.yd.	114
2	Burnt stone in clay foundation and basement	C.ft.	3,623
3	Burnt brick in clay superstructure	,,	3,124
4	Do mortar	,,	746
5	Burnt stone slabs 6" thick dressed nicely and fixed ...	S.ft.	591
6	Honnewood work wrought and put up with wood oiling ...	C.ft.	98·36
7	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	21·18
8	Ridge tiles set in mortar	R.ft.	58
9	Chunam plastering	Sqr.	74·84
10	Honnewood battened doors with iron clamps, hinges and bolts, etc., complete.	S.ft.	340
11	Honnewood battened windows with shutters, iron bars, hinges, etc., complete.	,,	·54
12	Honnewood battened ventilators with iron bars, hooks, etc., complete.	,,	55
13	Honnewood battened eave board 9"×1"	R.ft.	309
14	Chunam pointing	Sqr.	3·16
15	White washing 2 coats	,,	74·84
16	Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing, etc., complete.	,,	715
17	Flooring with 1½" thick Cudappah slabs over 3" concrete and cement pointing, etc.	,,	4·26
18	Silicate painting	,,	16·29
19	Tarring walls of latrine and wood work imbedded in walls ..	L. S.	...
20	Coping with burnt brick in chunam over compound wall and plastering, etc.	R.ft.	196
21	Flooring with gravel including consolidation, etc., complete ...	S.yd.	10
22	Chunam borders over roof	R.ft.	61
23	Constructing U shaped drain with burnt stone slabs with cement pointing, etc.	,,	251
24	Providing chimney over kitchen	Each	5
25	Do 1½" dia. galvanized drain pipe to drain water from latrine.	,,	10
26	Constructing seats in latrine with cement plastering ...	L. S.	...
27	Teakwood finials	Each	2
28	Do pendents	,,	4
29	Constructing cistern in kitchen with burnt stone slabs, cement pointing with plastering to sides, etc., complete.	L. S.	...
30	Providing mortar and pestle stones	L. S.	...

A. TANDONI RAO,
Executive Engineer.